

**SUBJECT: Maximum gas pipe installation without air test**

**EFFECTIVE DATE:** May 2002 **REVISED:** July 2004

**INTERPRETATION NUMBER:** ADM – 2.1204.4

**SEE ALSO:** 2003 UPC – Section 1204.4

**INTERPRETATION SUMMARY**

Staff has determined that air testing of gas pipe shall be mandatory for all gas piping that will be concealed, including crawl spaces and attics, no matter how minor. Screwed gas pipe up to 20' in developed length and containing no more than 5 fittings or valves in unconcealed locations shall not be required to be air tested.