SECTION 104 – MOBILIZATION

1. GENERAL

This item shall include, but not be limited to, preparatory work and operations to move personnel, equipment, supplies and incidentals to the project site; for establishment of all offices, building and other facilities necessary to work on the project and for all other work and operations that must be performed or costs incurred prior to beginning work on the various items on the project list.

2. MEASUREMENT AND PAYMENT

Payment for this work shall be made at the contract lump sum price for "Mobilization" according to the following table.

Mobilization Partial Payments		
Percent of Original	Pay Lesser of the Two	
Contract Amount	% of Mobilization	% of Original Contract Amount
Completed		
5	25	2.5
10	50	5.0
25	60	7.5
50	100	10.0
Accepted	100	NA

The Percent of Original Contract Amount Completed = the amount earned by the Contractor* divided by the total dollar value of the original contract (all bid items).

Rev: 24 March 2011 DRS 104-1

^{*}Do not include monies earned for "Mobilization", "Traffic Control (Lump Sum)", "Contractor Construction Staking" and "Stored Materials".