

SECTION 106 – CLEARING AND GRUBBING

1. GENERAL

This work shall consist of clearing, grubbing, removing and disposing of all vegetation and debris as shown on the plans and in accordance with Section 201 of the Standard Specifications.

All cleared vegetation and debris including stumps and roots shall be completely removed from the project site and disposed of in accordance with all applicable Federal, State and local ordinances.

If designated on the plans, large tree removal shall consist of the felling, cutting up, and disposal of trees greater 12 inches in diameter measured 2 feet above the natural ground level. The method of disposal shall be accomplished in accordance with all applicable Federal, State, and local ordinances.

2. MEASUREMENT AND PAYMENT

If designated on the bid form, payment for this work shall be made at the contract lump sum price bid for "Clearing and Grubbing" and the contract unit price bid per each for "Large Trees**Error! Bookmark not defined.**". Otherwise, no direct payment shall be made for this work as it shall be considered subsidiary to other bid items.